BRUHAT BANGALORE MAHANAGARA PALIKE

Item No. 67

APPROVED SCHEDULE - B

ation No: BBMP/ EE /Btp/Ten/02/2012-13 Dated: 15-05-2012

ork: Improvements of Road in Muneshwara Swamy Temple Road and Cross Roads at thahalli. in Ward No 07 Kodigehalli Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of A manjunath	
				In Figures	In Words
1	244.80	Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods Complete as per Specification and Directions of Engineer in charge of the Work	Cum	65.98	Rupees Sixty Five and Ninety Eight Paise Only
2	594.00	Removing BS Slab of drain and stacking. Complete as per Specification and Directions of Engineer in charge of the Work	Sqm	49.88	Rupees Forty Nine and Eighty Eight Paise Only
3	415.80	Refixing stone slabs of drains and pointing in CM 1:3. Complete as per Specification and Directions of Engineer in charge of the Work	Sqm	62.35	Rupees Sixty Two and Thirty Five Paise Only
4	340.80	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods Complete as per Specification and Directions of Engineer in charge of the Work	Cum	151.90	Rupees One Hundred Fifty One and Ninety Paise Only
5	42.60	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing Complete as per Specification and Directions of Engineer in charge of the Work	Cum	4134.80	Rupees Four Thousand One Hundred Thirty Four and Eighty Paise Only
6	12.00	Providing and constructing granite size stone masornry in foundation cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m.apart in each course including cost of materials, labour, curing Complete as per Specification and Directions of Engineer in charge of the Work	Cum	2968.13	Rupees Two Thousand Nine Hundred Sixty Eight and Thirteen Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of A manjunath	
				In Figures	In Words
7	20.00	Providing flush pointing to square rubble, course or uncoursed stone masonry with CM 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing Complete as per Specification and Directions of Engineer in charge of the Work	Sqm	83.68	Rupees Eighty Three and Sixty Eight Paise Only
8	178.20	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. (7.50cms thick)	Sqm	343.47	Rupees Three Hundred Forty Three and Forty Seven Paise
9	1.90	Providing and laying in position plain cement concrete of mix M15 with cement @ 240 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing Complete as per Specification and Directions of Engineer in charge of the Work	Cum	4683.67	Rupees Four Thousand Six Hundred Eighty Three and Sixty Seven Paise Only
10	30.00	Construction of embankment with approval material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications. (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) Complete as per Specification and Directions of Engineer in charge of the Work	Cum	154.17	Rupees One Hundred Fifty Four and Seventeen Paise Only
11	74.29	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC Works laid in 15cms thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3 with all lead and lift etc., complete (exclusive of cost of steel and fabrication charges) Ready mixed Cement concrete for Beams, Columns Staircase and Roof with M-20 (1:1.5:3) (Cement 320kg/cum) Complete as per Specification and Directions of Engineer in charge of the Work	Cum	5250.00	Rupees Five Thousand Two Hundred Fifty Only
12	1143.60	Providing and removing centering, shuttering, strutting, propping etc, and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour Complete as per Specification and Directions of Engineer in charge of the Work	Qtl	306.06	Rupees Three Hundred Six and Six Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of A manjunath	
				In Figures	In Words
13	31.37	Providing TMT. Steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and /or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, lobour, HOM of machinery Complete as per Specification and Directions of Engineer in charge of the Work	Sqm	7712.27	Rupees Seven Thousand Seven Hundred Twelve and Twenty Seven Paise Only
14	379.20	Providing and laying 10cms thick precast R.C.C. slabs (DATA RATE) Complete as per Specification and Directions of Engineer in charge of the Work	Sqm	1574.40	Rupees One Thousand Five Hundred Seventy Four and Forty Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92